

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-181-20027-00-00
Spot: NENWSE Sec/Twnshp/Rge: 14-6S-37W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: COOPER A Well #: 1
County: SHERMAN Total Vertical Depth: 4975 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

PROD Size: 4.5 feet: 4967 w/200 sxs cmt
SURF Size: 8.625 feet: 374 w/250 sxs cmt

4/6/04

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ROBERT C. PATTON Company: THOROUGHbred ASSOCIATES Phone: (316) 685-1512

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 05/25/2004 10:30 AM

Witness Type: COMPLETE (100%)
KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 374' w/250 sxs cement.
4 1/2" production casing set at 4967' w/200 sxs cement.
TD 4975'. PBTD 4925'.
Connected to 4 1/2" production casing - pumped 250 sxs cement with 500# hulls.
Max. P.S.I. 700#. S.I.P. 400#.
Connected to 8 5/8" surface casing - pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4607	4611		

RECEIVED
JUN 04 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 6-4-04

INV. NO. 2004061643

Form CP-2/3

MAY 26 2004

ASEROROMBIE DRLLG., INC.
 531 UNION CENTER
 WICHITA, KS.
 CONTR. CO. TOOLS

#1 COOPER
 SHERMAN

14-6-37
 NE NW 1/4

GEOLOGIST JACK WHARTON

FIELD WC (LLANOS SE DISC.)

X-5415 KB CM 11/14/77 CARD ISSUED 2/16/78 IP P 100 BOPD + 19% W

MARM 4607-11
 GR 25.9°

API 15-181-20,027

LOG	TOPS	DEPTH	DATUM
ANH		3078	+ 337
B ANH		3112	+ 303
HEEB		4229	- 814
TOR		4267	- 852
LANS		4283	- 868
STARK		4488	-1073
BKC		4546	-1131
MARM		4555	-1140
CHEE SH		4717	-1302
MLSS		4938	-1523
ITD		4975	-1560
RTD		4975	-1560

8-5/8" 374.44/250sx, 4 1/2" 4967.46/200sx
 DST (1) 4441-80/30-45-30-45, 5' O SPEAR
 M, SIP 1024-660#, FP 43-43#, 43-43#
 DST (2) 4585-4625/30-45-60-45, 1000'
 GIP, 720' GO, 240' OCM (GR 25°), SIP
 1410-1388#, FP 65-194#, 259-400#
 DST (3) 4626-4656/30-45-60-45, 125'
 CL O, 60' OCM (GR 28°), SIP 97-108#
 FP 54-76#, 86-108#
 DST (4) 4656-4717/30-30-60-45, 150'
 W/TR O, SIP 1582-1560#, FP 72-
 108-151#
 DST (5) 4780-4810/15-45-60-45, 1400'
 MSW, SIP 1088-1056#, FP 97-248-
 313-648#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)