

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-19014-00-02
Spot: NWNWSE Sec/Twnshp/Rge: 32-14S-2W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAGG Well #: 2
County: SALINE Total Vertical Depth: 3299 feet

Operator License No.: 6819
Op Name: SCOTT'S WELL SERVICE INC
Address: PO BOX 136
ROXBURY, KS 67476

PROD Size: 7 feet: 3398
SURF Size: 10.75 feet: 279

\$107²²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2004 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: JAY SCOTT Company: SCOTT'S WELL SERVICE INC Phone: (785) 259-7828

Proposed Plugging Method: Sand to 3250' c/w 7 sxs. Perf @ 450' & circ to surf. Perf @ 3295' - 3296-1/2'.

RECEIVED
KCC DISTRICT #2
JUN 1 2004

WICHITA, KS

Plugging Proposal Received By: RALPH TITTEL Witness Type: PARTIAL
Date/Time Plugging Completed: 05/25/2004 9:45 AM KCC Agent: RALPH TITTEL

RECEIVED
KANSAS CORPORATION COMMISSION

Actual Plugging Report:

Perfs:

JUN 04 2004

CONSERVATION DIVISION
WICHITA, KS

Sanded to 3250' and capped with 7 sacks of cement. Perforated 7" at 450'. Ran 2" tubing to 450' and circulated cement to surface. Pulled tubing and refilled with cement.

65 sacks of 60/40 posmix with 4% gel.

Remarks: ALLIED #15588

Plugged through: TBG

District: 02

Signed

Ralph Tittel (ret.)

(TECHNICIAN)

INVOICED

DATE 6-4-04

INV. NO. 20040611642