

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21171-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 1-32S-42W
2500 feet from S Section Line, 2600 feet from E Section Line
Lease Name: JOHNS Well #: 3-1
County: MORTON Total Vertical Depth: 5220 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4889 WITH 30 SX CMT
MSCC Size: feet: 3496 WITH 210 SX CMT
PROD Size: 7 feet: 5194 WITH 265 SX CMT
SURF Size: 9.625 feet: 1482

#169⁶⁵

Well Type: GSO UIC Docket No: Date/Time to Plug: 05/27/2004 12:00 AM

Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE

Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SERVICES Phone: (303) 595-3331

Proposed Plugging Method: CIBP @ 4889' WITH 30 SX CMT. PLUG AT 1708' WITH 125 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 05/27/2004 7:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 5155'. SET CIBP @ 4889' WITH 30 SX CMT. 1ST PLUG CIRCULATED HOLE WITH MUD TO 1708' & PUMP 125 SX CMT. 2ND PLUG PULLED UP TO 600' & PUMPED 50 SX CMT. 3RD PLUG PULLED UP TO 40' & PUMPED 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5074	5092		
4996	5010		

RECEIVED
JUN 04 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 1708' OF 7" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUN - 2 2004
KCC Dodge City

Signed

Kevin Strube

INVOICED
DATE 6-4-04
INV. NO. 20040616-39

Form CP 2/3
[Signature]