

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20159-00-01
Spot: SWSW Sec/Twnshp/Rge: 4-35S-21W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: KATE Well #: 1
County: CLARK Total Vertical Depth: 5708 feet

Operator License No.: 5050
Op Name: HUMMON CORPORATION
Address: 950 N. TYLER
WICHITA, KS 67212

CIBP Size: feet: 4275 WITH 2 SX CMT
PROD Size: 4.5 feet: 4623 WITH 200 SX CMT
SURF Size: 8.625 feet: 819 WITH 525 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 4275' WITH 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2004 4:15 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 4275' WITH 2 SX CMT. 05/21/04: PULL CASING TO 900' & SPOT 10 SX GEL & 50 SX CMT. PULL CASING TO 400'. TRIED TO LOAD HOLE. WOULD NOT LOAD. SPOT 40 SX CMT. 05/24/04: TAG CMT WITH TUBING AT 290'. TRIED TO LOAD. HOLE WOULD NOT LOAD. FL AT 100'. PUMPED 10 SX HULLS - 10 SX GEL - 75 SX CMT WITH 3% CC. CIRCULATED CMT TO SURFACE. 05/25/04: WELL CHECKED CMT AT SURFACE.

Perfs:


Top	Bot	Thru	Comments
4330	4336		

RECEIVED
JUN 02 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3450' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

[Signature]
(TECHNICIAN)

INVOICED

DATE 6-2-04

INV. NO. 2004076628

Form CP-118 *[Signature]*