

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16396-00-00  
Spot: S2SESW Sec/Twnshp/Rge: 12-16S-14W  
330 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: SAUSSEN Well #: 3  
County: BARTON Total Vertical Depth: 3352 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

PROD Size: 7 feet: 3343 60 SX CMT  
SURF Size: 10.75 feet: 888

#108 94

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2004 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: BOB GRANT Company: BEEREXCO, INC. Phone: (785) 628-6101

Proposed  
Plugging  
Method:

[Empty box for Proposed Plugging Method]

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2004 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

05-25-2004 - Perforated at 1625' - 825' - 375'.  
Ran tubing to 3326'.  
Pumped 110 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
Pulled to 1600' - pumped 160 sxs cement with 300# hulls.  
Pulled to 500' - pumped 75 sxs cement.  
POOH. Let set overnight.  
05-26-2004 - 9:00 AM. - Tagged cement at 1650'.  
Circulated with 150 sxs cement with 300# hulls.  
POOH.  
Pumped 40 sxs cement down casing.  
Cement circulated up annulus.  
Max. P.S.I. 300#. S.I.P. 100#.  
Filled cellar with 20 sxs cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 01 2004

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

Form CP-2/3

DATE 6-2-04  
BY 20040616/25

MAY 27 2004

WAKEFIELD ET AL #3 SAUSSEN 12-16-14w  
CS2 SE SW

Contr. \_\_\_\_\_ BARTON \_\_\_\_\_ County

E 1925 Comm. 6-7-15 Comp. 7-21-15 IP 553 BOPD

Tops	Depth	Datum	Casing
			15" 379
ANHY	894		7" 3343
			10 3/4" 888
LAUS	3140		
ARB	3343		
TD	3352		

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

11/10/15