

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20384-00-00
Spot: NENWSW Sec/Twnshp/Rge: 22-10S-25W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BRUNGARDT A Well #: 4
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 4090 w/125 sxs cmt
SURF Size: 8.625 feet: 214 w/175 sxs cmt

#132⁹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2004 8:00 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 800# hulls.
Planned to pull casing from 1000' to surface.
CIBP at 3860' - 3883' - 3888'. Casing leaks.
Squeeze at 1990' - 2010'-2095' - 2300' - 3041'-3069' w/250 sxs;
3029'-3057' w/50 sxs; 1515'-1545' w/150 sxs; 3046'-3078' w/200 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH and tagged sand on bottom at 3650'.
Pulled tubing to 3600' - pumped 60 sxs cement with 400# hulls mixed in.
Pulled tubing to 2650'. Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 200 sxs hulls mixed in.
Some fluids circulated out of casing near surface.
Decided not to pull casing.
Pulled tubing to 1350' - pumped 85 sxs cement with 200# hulls to circulate cement to surface.
Pulled tubing and rigged up to 5 1/2" casing with a swedge. Pumped 20 sxs cement. S.I.P. 100#.
Cement blew out of hole in casing near surface.
Tied onto backside and pumped 110 sxs 60/40 pozmix.
Max. P.S.I. 0#. S.I.P. 0#.
Cement was near surface - will cut off and ready mix backside if needed.

Perfs:

Top	Bot	Thru	Comments
4004	4006		
3983	3990		
3962	3967		
3904	3906		
3865	3867		
3820	3826		
3041	3069		
3029	3037		
2010	2025		

RECEIVED
JUN 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #5972.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 6-3-04

INV. NO. 2004061632

Form CP-2/3

JUN 02 2004

DERRICK-AMERICAN OIL, INC. #4 BRUNGARDI "A" 22-10-25W
 WICHITA, KANSAS NE NW SW
 CONTR GABBERT-JONES CTY GRAHAM
 GEOL JIM THOMPSON FIELD AMBROSE

E 2535 RB CM 10/12/70 ^{CARD}ISSUED 12/3/70 IP P 144 BOPD N/W
 LKC 3962-67 & 3983-
 90 GR 41

API 15-065-20,384

SMP	TOPS	DEPTH	DATUM	
HEEB		3785	-1250	8 5/8" 214/175sx; 5 1/2" 4090/125sx
TOR		3807	-1272	DST(1) 3791-3817/30", 3120'CO, BHP 1340-1330#, FP 255-960#
LKC		3822	-1287	DST(2) 3816-40/1', 3180'CO, 150'W, SHP 1345-1340#, FP 585-1280#
RTD		4090	-1555	DST(3) 3839-3880/1', 3520'CO & 225'WTR, BHP 1385-1385#, FP 905-1305#
				DST(4) 3880-3925/1', 120'GIP, 120'HOCM, 130'MO, 260' CO, 470'OCW, BHP 1315-1300#, FP 75-485#
				DST(5) 3951-3990/1', 3570'CO, BHP 1305-1290#, FP 370-1150#
				DST(6) 4004-4015/1', 1560'GIP, 1020'OIL, 120'WTR, BHP 589-508#, FP 64-322#
				DST(7) 4013-4036/1', 65'HOCM, SHP 128-111#, FP 64-64#

MICT, PF 3962-67, SWB GSO NAT, PF 3983-90, SWB 8 TO 10 BOPH/1 1/2 HRS FROM BOTH ZONES, POP

NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

1310161