

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00399-00-00  
Spot: NENENESW Sec/Twnshp/Rge: 12-24S-35W  
2540 feet from S Section Line, 2540 feet from W Section Line  
Lease Name: GARDEN CITY F Well #: 1  
County: KEARNY Total Vertical Depth: 2726 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

PROD Size: 5.5 feet: 2720 WITH 900 SX CMT  
SURF Size: 8.625 feet: 800 WITH 400 SX CMT  
\$8860

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/13/2004 11:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 35 SX CMT. MUD SPACER TO 850'. PUMP 20 SX CMT FROM 850-800'. PUMP 40 SX CMT AT 613'. PUMP 10 SX CMT AT 0-40'.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/13/2004 5:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2694'. PUMPED DOWN 5 1/2" 500# HULLS & 35 SX CMT. DISPLACED WITH MUD TO 850'. PUMPED 20 SX CMT. DISPLACED WITH 14 BBL MUD. 1ST PLUG PULL TO 640' & PUMPED 40 SX CMT. DISPLACED WITH 10 BBL MUD. 2ND PLUG PULL CASING TO 40' & PUMPED 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2564	2582		
2501	2518		
2460	2478		
2440	2456		
2410	2418		

RECEIVED  
JUN 02 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 648' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAY 25 2004  
KCC Dodge City

Signed Kevin D Strube

(TECHNICIAN)

INVOICED

DATE 6-2-04

INV. NO. 2004061630

Form 1/3