

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00080-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 10-23S-35W
2540 feet from N Section Line, 2540 feet from E Section Line
Lease Name: MILLER K Well #: 1
County: KEARNY Total Vertical Depth: 2675 feet

\$86⁹⁴

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

PROD Size: 5.5 feet: 2673 WITH 700 SX CMT
SURF Size: 8.625 feet: 480 WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/12/2004 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HOROTN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 35 SX CMT & 500# HULLS. PUMP CMT FROM 800' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2004 1:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2650'. PUMPED DOWN 5 1/2" 500# HULLS & 35 SX CMT. MUD SPACER TO 800'. CMT FROM 800' TO 0' WITH 115 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2630	2648		
2582	2588		
2566	2574		
2532	2546		
2510	2526		

RECEIVED
JUN 02 2004
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAY 25 2004
KCC Dodge City

Signed

Kevin Strube

(TECHNICIAN)

INVOICED

DATE

6-2-04

INV. NO.

2004061630

Form 2/03