

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20189-00-00
Spot: E2 Sec/Twnshp/Rge: 15-21S-32W
2640 feet from N Section Line, 1320 feet from E Section Line
Lease Name: LANDGRAF B1-15 Well #: B1-15
County: FINNEY Total Vertical Depth: 2775 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

PROD Size: 4.5 feet: 2774 WITH 500 SX CMT
SURF Size: 8.625 feet: 390 WITH 300 SX CMT

\$90¹⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/13/2004 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: FILL 4 1/2" CASING WITH CMT TO SURFACE. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2004 1:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2735'. PUMPED DOWN 4 1/2" CASING 400# HULLS & 125 SX CMT. MAXIMUM PRESSURE 1500#. SHUT IN PRESSURE 1000#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 100 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN PRESSURE 200#.

Perfs:


Top	Bot	Thru	Comments
2692	2702		

RECEIVED
JUN 02 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed _____

Kevin D Strube

(TECHNICIAN)

INVOICED

DATE 6-2-04

INV. NO. 2004061626

Form *[Signature]*