

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-01536-00-01
Spot: N2NENW Sec/Twnshp/Rge: 27-16S-13W
4950 feet from S Section Line, 3200 feet from E Section Line
Lease Name: MORRISON B Well #: 1
County: BARTON Total Vertical Depth: 3499 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

PROD Size: 5.5 feet: 3493 150 SX CMT
SURF Size: 8.625 feet: 344 200 SX CMT

113 72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2004 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JAMES L MORTON Company: HARTMAN OIL CO., INC. Phone: (620) 791-7187

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2004 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2900' and dumped 5 sxs cement.
Cut off at 2050'.
Pulled to 1650' and pumped 115 sxs 60/40 pozmix - 6% gel with 300# hulls.
Pulled to 900' and pumped 65 sxs cement with 200# hulls.
Pulled to 300' and circulated with 65 sxs cement with 100# hulls.

Perfs:

Top	Bot	Thru	Comments
3230	3233		
3210	3218		
3186	3195		
2964	2968		

RECEIVED
MAY 24 2004
KCC WICHITA

Remarks: GRESSEL OILFIELD SERVICES-CEMENTING.

Plugged through: CSG

District: 04

HP

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 5-24-04
INV. NO. 2004061592

MAY 21 2004

HUPFER OIL & GAS
HAYS, KS 67601

27-16 -13W
100'E, C N/2 NE NW

#1-B MORRISON OWWO

site: 7-1/2 N & 3/4 E OF HOISINGTON, KS
contr: H-30 DRILLING, INC
geol: BANDALL KILIAN

city: BARTON
field: TRAPP

API 15-009-01946

536-00-01

fr date 09/25/89 spd date 10/17/89 drig comp 10/18/89 card issued 12/06/89 last revised 12/06/89

ELV: 1959 KB LOG
tops.....depth/datum
*ANH882 +1077
TOP.....2774 -815
HEEB.....3085 -1128
*TOR.....3101 -1142
BR LM3170 -1211
LANS.....3178 -1219
BKC.....3410 -1451
ARB.....3442 -1483
RTD OLD.....3445 -1488
LTD.....3499 -1540
DDTD.....3499 -1540
*SAMPLE TOP

IP status:
OIL, P 8 BO & 8 BWPD, LKC 3210-3263 OA,
NOTE: ELEV ON OLD WELL WAS 1954 KB, 1949 EGL;
CORRECTION: 11/1/89 - ORIG FR AS C N/2 NE NW; WAS
#1 MORRISON OWWO
OLD INFO: OPERATOR WAS BIRMINGHAM-BARTLETT
DRILLING, 1 MORRISON "B", SPD 04/23/64., 05/01/64
8-5/8" 344/200SX, D&A, ARB, (CARD ISSUED 05/07/64)
CONTR: BIRMINGHAM-BARTLETT DRILLING
GEOL: JACK CHILDERS
OLD LOG TOPS: HEEB 3087 (-1128), BR LM 3172 (-1213),
LANS 3180 (-1221), ARB REW 3446 (-1492), ARB 3451 (-
1482)

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

HUPFER OIL & GAS
HAYS, KS 67601

27-16 -13W
100'E, C N/2 NE NW

#1-B MORRISON OWWO

NO CORES

DST (1) 3177-3259 (LKC), / OP 120", 600' GIP, REC 130' SLJ OIL & GCM, SIT 15" ISIP 795#
FSIP 561# IFP 70# FFP 155#

DST (2) 3304-3344 (ARB), / OP 25", REC 10' M ISIP 0# FSIP 0# IFP 0# FFP 0#

NEW INFO: FR 09/25/89 , RE-ENTERED 10/17/89 WSH DWN TO 3445, DD 3499 TD, NO DSTS
RUN, LOGGED DC 10/18/89 CSG: SET 5-1/2" 3493 / 150 SX MICT - CO, PF (LKC) 3210-3218, W
/ 2 SPF, AC 1200 GAL (15% NE), SWB 8 BFPH (60% OIL), PF (LKC) 3259-3263, W / 2 SPF, AC
1200 GAL (15% NE), SWB 6 BOPH, PF (LKC) 3230-3233, W / 2 SPF, AC 1000 GAL (15% NE),
SWB 7 BFPH (38% OIL), TST ALL ZNS & SWB 22 BFPH (75% OIL), SET 2-7/8" TBG AT 3400, NO
PKR, POP, P 8 BO & 8 BWPD, GTSTM (GR 36), 11/8/89

5-64

MAP NO

SEC. 27-16S-13W

STATE Kansas COUNTY Barton

LOC N/2 NE NW

OPER Birmingham-Bartlett Drilling Co., Wichita, Kans

WELL #1 NAME Morrison "B"

WELL Trapp, Ext.

1949

1951

1954

CO. tools

Jack Childers

INT. PID 3425 test

DATE 4-21-64

5-12-64

3445 Arb.

D&A

8-5/8" @344' w/200 Sx.

KB Spl Tops:

Anh	882 + 1072	Lans	3175 -1221
Hb	3082 -1128	Cg	3404 -1450
Tor	3101 -1147	Arb	3441 -1487
BL	3166 -1212	RTD	3445 -1491

DST #1(Lans) 3177-3259, Op 2 hrs, 600' GIP, R 130' SO&GCM, ISIP
795#/20', IFP 70# FFP 155#, FSIP 561#/15'.

DST #2(Lans) 3304-3344, Op 25', R 10' M, All press. 0#.

RTD 3445', No log, D&A 4-30-64 COMPLETED 5-5-64.