

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21173-00-00
Spot: SESESE Sec/Twnshp/Rge: 2-32S-42W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: BOEKHAUS Well #: 1-2
County: MORTON Total Vertical Depth: 5200 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4900 WITH 30 SX CMT
MSCC Size: feet: 3059
PROD Size: 7 feet: 5190 WITH 205 SX CMT
SURF Size: 9.625 feet: 1460 WITH 510 SX CMT

16900

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 05/06/2004 10:00 AM

Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE

Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SVCS Phone: (713) 627-6814

Proposed Plugging Method: SET CIBP ABOVE TOP PERFORATIONS WITH 10 SX CMT ON TOP. PUMP 50 SX CMT @ CASING SHOOTOFF POINT. PLUG AT 1500' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 05/06/2004 6:00 PM

Witness Type: NONE
KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 5146'. CIBP @ 4900' & 30 SX CMT. 1ST PLUG AT 2030' WITH 50 SX CMT. 2ND PLUG AT 1460' WITH 75 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 40-0' WITH 15 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5024 | 5050 | | |
| 4973 | 4984 | | |
| 4947 | 4964 | | |

RECEIVED
JUN 02 2004
KCC WICHITA

Remarks: USED COMMON CLASS H CMT BY EAGLE WELL SERVICE. RECOVERED 2030' OF 7' CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY 24 2004
KCC Dodge City

Signed

Steve Durrant
(TECHNICIAN)

INVOICED

6-2-04
2004/06/27