

RECEIVED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD KCC WICHITA
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/21/04 (Date)

by: Jay Pfeifer w/ KCC in Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

2969-73,3242-46,3257-60 Depth to Top: _____ Bottom: _____ T.D. 3750

3301-03,3427-31 Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-22,680 - 00 - 00

Lease Name: Johnson E

Well Number: #6

Spot Location (QQQQ): C S/2 - SE - NW - SE

330 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 29 Twp. 11 S. R. 18 East West

County: Ellis County

Date Well Completed: 12/4/1981

Plugging Commenced: 5/21/04

Plugging Completed: 5/21/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	241	8 5/8	241	0
	Production	Surface	3747	5 1/2	3747	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

102 jts 2 7/8" tbg @ 3200', RU Allied cmt, hook up to tbg mix & pump 10 sx gel spacer, mix & pumped 50 sx 60/40 10% gel & 300# hulls, FL.

Circ to surface, pull 41 jts tbg @ 1920' mix & pumped 60sx & 200# hulls, pull 19 jts to 1300' mix & pumped 80 sx circ. cmt to surface, pulled tbg

out of hole. Put on 5 1/2" swage mix & pump 25 sx cmt, circ around annulus, shut in annulus squeezed another 10 sx in pres to 1000# & shut in.

Used 225 sx 60/10 10% gel 500# hulls, 10 sx gel. Job complete @ 12:30pm. Witnessed by Jay Pfeifer w/ KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 1st day of June, 2004

Kristin Grady My Commission Expires: 2/06/08
Notary Public

