

STATE OF KANSAS
 RECEIVED COMMISSION
 J. S. Market, Room 2078
 Wichita, MAY 27 2004

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-025-21195-00-01

LEASE NAME Tuttle

WELL NUMBER 3-4

~~1980~~
~~1930~~ ¹⁹³⁰ Ft. from S Section Line

360 W
 Ft. from E Section Line

SEC. 4 TWP. 35S RGE. 21W (E) or (W)

COUNTY Clark

Date Well Completed 6-15-00

Plugging Commenced 5-18-04

Plugging Completed 5-20-04

KCC WICHITA

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR HUMMON CORPORATION

ADDRESS 950 N. Tyler Road Wichita, Kansas 67212-3240

PHONE# (316) 773-2300 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-10-04 (date)

by Steve Middleton (KCC District Agent's Name).

ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>384</u>	<u>8-5/8"</u>	<u>384'</u>	<u>None</u>
<u>prod</u>			<u>5730</u>	<u>4-1/2"</u>	<u>5730'</u>	<u>4000'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.
Bridge Plug set @4375' with 2 sacks cement on top. Cut casing loose @4000', pulled up to 900', pumped 10 sacks gel, 100% hulls and 50 sacks cement, pulled up to 400', pumped 40 sacks cement and 100% hulls, pulled up to 40' and topped off with 40 sacks cement 60/40 pos. 6% ge
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc. Hummon Corp

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 25th day of May, 20 04

[Signature]
 Notary Public

My Commission Expires:

