

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD JUN 02 2004 K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: M.E. Klein & Associates, Inc.

Address: 1818 West Lindsey Building C-180 Norman, OK. 73030

Phone: (405) 627-0669 Operator License #: 31933

Type of Well: ENHR Docket #: E-25618 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 4-20-04 (Date)

by: Herb Deines District Supervisor Hays, Ks. (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3706 Bottom: 3930 T.D. 4000 3950

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-065-22502 00-00

Lease Name: Keith

Well Number: 2

Spot Location (QQQQ): NW - SE - NE -

3464 Feet from North / South Section Line

825 Feet from East / West Section Line

Sec. 29 Twp. 8 S. R. 24 East West

County: Graham

Date Well Completed: 12-23-88

Plugging Commenced: 5-4-04

Plugging Completed: 5-4-04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include LKC OIL WATER with casing details.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CIBP @ 3550'. Ran tubing in well-tagged plug pumped 16 sks of gel followed with 20 sks of cement put on top of plug pulled tubing to 1275' mixed 80 sks of cement circulated cement to surface, pulled tubing out filled casing to surface- casing filled put 500# pressure on, closed in casing. Pumped 10 sks down annulus of 8 5/8 and 4 1/2 filled put 500# pressure on annulus, shut in annulus. plugging completed.

Name of Plugging Contractor: Allied Cementing, Inc. License #: 99996

Address: Russell, Ks.

Name of Party Responsible for Plugging Fees: M.E. Klein & Associates, Inc.

State of OK. County, ss.

Carl Zimmerman (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carl Zimmerman (Address) 1116 East 8th St. Hays Kansas. 67601

SUBSCRIBED and SWORN TO before me this 28th day of May, 2004

Judy Ziegler Notary Public My Commission Expires: 7/28/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOTARY PUBLIC JUDY ZIEGLER NOTARY PUBLIC STATE OF KANSAS My App. Exp. 7/28/07

Handwritten signature