

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline
Address: 3800 Frederica Street Owensboro, Kentucky
Phone: (270) 852-5000 Operator License #: 33097

Type of Well: Gas Storage Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: September 17, 2003 (Date)
by: Jack Robison (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Bush City Ss. Depth to Top: 510' Bottom: 548' T.D. 548'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-091-19077-00-00
Lease Name: Craig #25 Storage
Well Number: Craig # 25
Spot Location (QQQQ): SE-NE-SW
1650' Feet from North / South Section Line
2970' Feet from East / West Section Line
Sec. 23 Twp. 12 S. R. 23 East West
County: Johnson
Date Well Completed: 5/19/2004
Plugging Commenced: 3/11/2004
Plugging Completed: 3/11/2004

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|------------------|--|------|------|---------------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Bush City Ss. | Gas / <u>Gas</u> | 3' | 496' | 7" | cemented 496' | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

All tubulars pulled from well-bore. Plugged solid with Class A cement, from surface to total depth.

Ran 2" to through retainer and pumped 50 sks. 350# stabilized / 150# below retainer. Pumped through 2" and filled to surface. Tied onto 7" and pumped into perms.. SIP@ surface 25 #.

Set cement retainer @ 466'. Perforated 58', 150', 3 shts./ft.

Total Cement: 267 sks. Class A cement. Cement below retainer 50 sks. Cut and cap.

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66270

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

Charles C. McConnell / D. Mark Rouse

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) 3800 Frederica Street Owensboro, Kentucky 42304

SUBSCRIBED and SWORN TO before me this 21st day of May, 20 04

Karen J. Hollman My Commission Expires: 8-26-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 24 2004

CONSERVATION DIVISION
WICHITA, KS

for