

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-147-30192-00

LEASE NAME KENT

WELL NUMBER 1

SPOT LOCATION SE/4 SE/4

SEC. 22 TWP. 1 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/25/85

Plugging Completed 9/25/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Twin Eagle Petroleum Corp.

ADDRESS 2431 E. 61st St., Ste 480, Tulsa, OK 74136

PHONE # (918) 745-9143 OPERATORS LICENSE NO. 9058

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? See attached

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing-Kansas City Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3593

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	200	0
				4-1/2"	3592	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. See Attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
Address P. O. Box 31 Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Thomas C. Mach (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
2431 E. 61st Street, Ste 480  
(Address) Tulsa, OK 74136

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1985

Notary Public

My Commission expires: 12-09-85

DEC 23 1985

12-23-85

CONSERVATION DIVISION

Form CP-4  
Revised 01-84



15-147-30192-00-~~00~~<sup>02</sup>

KENT #1 9/25/85

Hole In Casing 1179'

Used total of 400 sacks of 60-40 Poz mix with 10% gel, 3% cc, ¼ # flo cele and 6 sacks of hulls, 20 sacks of gel.

Pumped 50 sacks of cement with hulls down 4½" casing.

Pumped 10 sacks of gel with hulls.

Pumped 125 sacks of cement with hulls.

Pumping Press 600 PSI

Shut In Press 200 PSI

Pumped 75 sacks of cement with hulls down 8 5/8 casing.

Pumped 10 sacks of gel with hulls down 8 5/8 casing.

Pumped 125 sacks of cement with hulls down 8 5/8 casing.

Pumping Press 400 PSI

Shut In Press 150 PSI

This well was plugged at 3:00 p.m. and witnessed by Dennis Hammel of the Kansas Corporation Commission.

STATE OF KANSAS CORPORATION COMMISSION

DEC 23 1985

CONSTRUCTION DIVISION  
TOPEKA, KANSAS