

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED KANSAS CORPORATION COMMISSION JUN 01 2004 06-01-04 Type or Print on this Form Form must be Signed Conservation Division Blanks must be Filled WICHITA, KS Form CP-4 December 2003

Lease Operator: Wolverine Environmental Production LLC.

Address: 1 Riverfront Plaza, Grand Rapids, Michigan 49503

Phone: (616) 458-1150 Operator License #: 33240

Type of Well: D&A Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/7/04 (Date)

by: Mike Hrffern (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

None - Dry Hole Depth to Top: Bottom: T.D. 2022

API Number: 15-11120421000

Lease Name: Jones

Well Number: A2-29

Spot Location (QQQQ): NE SE NW SW 340' Feet from North / South Section Line

2300' Feet from East / West Section Line

Sec. 29 Twp. 17 S. R. 13 East West

County: Lyon

Date Well Completed: 7/14/03

Plugging Commenced: 5/8/04

Plugging Completed: 5/8/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Mineral, Rowe, Dw, and L. Riverton.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

RIH w/tbg. work-string tagged btm. pulled up 1 jnt..MIRU Consolidated filled csg. w/gel. Pulled up just above top perforation and set a 50' cement plug 1680'-1630'. Gel pad 1630-643 . POOH w/tbg..MIRU Log Tech & shot off csg. at 643'. Set cement plug 643'-593', gel pad to 350' then cement plug 350' to surface. (Cement was 50-50 poz w/2% gel 14.5# to 15.5#)

Name of Plugging Contractor: Consolidated Oil Well Service License #: 34440-31440

Address: 2631 Eisenhower Ave. , Ottawa, Ks. 66067

Name of Party Responsible for Plugging Fees: Wolverine Environmental Production LLC

State of Oklahoma County, Tulsa, ss.

Joel Friedman/Exact Eng. Inc. Pet. Eng. Agent (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Joel Friedman

(Address) 415 S. Boston, Ste 734, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 28 day of May, 2004

Janice R. Weaver Notary Public My Commission Expires: 5-1-2005 # 01006609

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202