

STATE OF KANSAS
STATE CORPORATION COMMISSION
5. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-167-072080000

LEASE NAME ROUBACK

WELL NUMBER 9

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 14 RGE. 15 (X) or (W)

COUNTY RUSSELL

Date Well Completed 7-17-37

Plugging Commenced 6-2-2004

Plugging Completed 6-2-2004

RECEIVED

JUN 04 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MAI OIL OPERATIONS, INC.

ADDRESS P.O. BOX 33, RUSSELL, KS. 67665

PHONE (785) 483 2169 OPERATORS LICENSE NO. 5259

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

plugging proposal was approved on 6-1-2004 (date)

CASE MORRIS (KCC District Agent's Name).

CO-1 filed? _____ If not, is well log attached? _____

Producing Formation GORHAM SAND Depth to Top 3290' Bottom 3292' T.D. 3292'

depth and thickness of all water, oil and gas formations.

GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>		<u>923'</u>	<u>0'</u>	<u>10"</u>	<u>923</u>	<u>0</u>
<u>Prod.</u>		<u>3290'</u>	<u>0'</u>	<u>5 1/2"</u>	<u>3290</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was used and the method or methods used in introducing it into the hole. If cement or other plug used, state the character of same and depth placed, from _____ feet to _____ feet each section. holes in CSG FROM 3100' TO 1300', RUN TBG TO 2011' MIX 260 SKS 60-40POZ 10% GEL & 500# HULLS. CEMENT CIRC TO SURFACE. PULL TBG, HOOKUP TO CSG, AND MIX 140 SKS 60-40 POZ AND 300# HULLS. MAX PSI 400#, ISIP 250#. WELL PREVIOUSLY SQUEEZED @ 470' W/ 100 SKS CMT & SQUEEZED @ 498' W/100 SKS CMT.

Plugging Contractor ALLIED CEMENTING License No. 99996

Address 24 S. LINCOLN, RUSSELL, KS. 67665

OF PARTY RESPONSIBLE FOR PLUGGING FEES: MAI OIL OPERATIONS, INC.

STATE OF KANSAS COUNTY OF RUSSELL, KS., ss.

ALLEN BANGERT

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Allen Bangert

(Address) P.O. BOX 33, RUSSELL, KS. 67665

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 2004

Verna May Hutchings
Notary Public

My Commission Expires: April 10, 2005

