

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-19060-00-00
API NUMBER Drilled 1960

LEASE NAME O'Neil
WELL NUMBER 1
SPOT LOCATION SW NE SW
SEC. 22 TWP. 1 RGE. 18 (W) or (E)
COUNTY Phillips
Date Well Completed 12-60
Plugging Commenced 11-16-84
Plugging Completed 11-16-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation
ADDRESS Box 520 Great Bend, Kansas 67530

PHONE # (316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well INPUT
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached? Sent with Form CP-1

Producing formation LKC Depth to top 3328 bottom 3381 T.D. 3573

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3328	81	8 5/8	200	None
				4 1/2	3573	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Cemented w/450 sx 50/50 pozmix, 8% gel, 1/4# Flocele, mix 300 sx 50/50 pozmix, 8% gel, 1/4# Flocele down 4 1/2, SI pressure 450#, mix 150 sx 50/50 pozmix, 8% gel, 1/4# Flocele, 5 sx hulls down Annulus, SI pressure 350# Done 11:30 A.M.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.
Address Box 47 Oberlin, Kansas

STATE OF Kansas COUNTY OF Phillips

Phil A. Emig (employee of operator) of 11-28-84
(operator) of above-described well, being first duly sworn on oath, says: NOV 28 1984
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Phil A. Emig
(Address) Phil A. Emig



SUBSCRIBED AND SWORN TO before me this 27 day of November, 1984
Ramona L. Dunlap
Notary Public

My Commission expires: 1-23-88