

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-00419-00-01
 API NUMBER _____

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Schluntz
 WELL NUMBER 4
 _____ Ft. from S Section Line
 _____ Ft. from E Section Line

LEASE OPERATOR Graham-Michaelis Corporation
 ADDRESS P.O. Box 232 Russell, KS. 67665
 PHONE#(913) 483-3136 OPERATORS LICENSE NO. 5134

SEC. 30 TWP. 1S RGE. 18W (E) or (W)
 COUNTY Phillips
 Date Well Completed _____
 Plugging Commenced _____
 Plugging Completed 10-4-90

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on _____ (date)
 by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3615'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	194'	none
				4 1/2"	3614'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran wireline to T.D. pumped down casing 8 bbls. water. Pumped down casing 50 sacks down common cement and 110 sacks 65/35 poz 8% gel, Max pressure 100lbs. closed w/800 lbs. holding.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporation 10-19-90
OCT 19 1990

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 18 day of Oct, 19 90

Irene Herzberg
 Notary Public

My Commission Expires: _____



DRILLER'S LOG

15-147-00419-00-01

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

COMMENCED:
COMPLETED:

FELDT MAYTAG AND COMPANY
LEBEN DRILLING, INC.
SCHLUNTZ #4
C NE NE SEC. 30-1S-18W
PHILLIPS COUNTY, KANSAS
12-16-59
12-24-59

0	40	Surface Clay
40	70	Shale
70	240	Shale
240	685	Shale and Shells
685	1485	Shale, Sand and Shale
1485	1770	Shale
1770	1790	Anhydrite
1790	1795	Anhydrite
1795	2105	Shale
2105	2225	Shale and Shells
2225	2350	Shale
2350	2495	Lime and Shale
2495	2670	Lime and Shale
2670	2785	Shale and Shells
2785	2980	Shale and Lime
2980	3100	Shale and Lime
3100	3165	Shale and Lime
3165	3270	Shale and Lime
3270	3330	Lime and Shale
3330	3382	Shale and Lime
3382	3435	Shale and Lime
3435	3485	Lime and Shale
3485	3550	Lime and Shale
3550	3615	Lime
	<u>3615</u>	<u>Rotary Total Depth</u>

RECEIVED

JUL 5 1960
Graham-Williams Corp
Wichita, Kansas

RECEIVED
JAN 3 1960
C. L. F. [initials]
J. B. M. [initials]

Set 8 5/8" surface casing @ 194' with 165 sacks Sunset cement.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schluntz #4, located C NE NE of Section 30, Township 1 South, Range 18 West, Phillips County, Kansas, as reflected by the files of Leben Drilling, Inc.

James M. Battin

JAMES M. BATTIN

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

RECEIVED
JUL 6 1960
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of December, 1959.

Juanita M. Green

Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963