

RECEIVED
KANSAS CORPORATION COMMISSION

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JUN 01 2004
6-01-04
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Wolverine Environmental Production LLC.
Address: 1 Riverfront Plaza, Grand Rapids, Michigan 49503
Phone: (616) 458-1150 ext119 Operator License #: 33240
Type of Well: D&A Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/7/04/ (Date)
by: Mike Heffren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None - Dry Hole Depth to Top: _____ Bottom: _____ T.D. 2142

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-111-20418-00-00
Lease Name: Whittington
Well Number: C4-26
Spot Location (QQQQ): AP 30' N 70' W 4' E N 2' E S E
~~NE SE NW SW~~
2010 Feet from North / South Section Line
400 Feet from East / West Section Line
Sec. 26 Twp. 17 S. R. 12 East West
County: Lyon
Date Well Completed: 7/19/03
Plugging Commenced: 5/7/04
Plugging Completed: 5/7/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>V Shale / Surf</u>	<u>water</u>	<u>1750.5</u>	<u>1751.5</u>	<u>8.625</u>	<u>101</u>	<u>50</u>
<u>Bw Prod</u>	<u>water</u>	<u>1984.5</u>	<u>1985.5</u>	<u>5.500</u>	<u>2140'</u>	<u>110</u>
<u>Cw</u>	<u>water</u>	<u>1993.0</u>	<u>1994.0</u>			
<u>Dw</u>	<u>water</u>	<u>1998.5</u>	<u>1999.5</u>			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/tbg. work-string tagged pulled up 1 jnt..MIRU Consolidated filled csg.w/gel. Pulled up just above top perforation and set a 50' cement plug 1732'-1682'.POOH w/tbg..MIRU Log Tech & shot off csg. at 491'.Set cement plug 491'-441' then gel pad to 350'& set cement plug from 350' to surface. (cement 50-50 poz w/2% gel 14.5#-15.5#)

Name of Plugging Contractor: Consolidated Oil Well Service License #: 34440 31440

Address: 2631 Eisenhower Ave. , Ottawa, Ks. 66067

Name of Party Responsible for Plugging Fees: Wolverine Environmental Production LLC

State of Oklahoma County, Tulsa, ss.

Joel Friedman/Exact Eng.Inc. Pet.Eng.Agent (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Joel Friedman
(Address) 415 S. Boston, Ste 734, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 28 day of May, 2004
Janice R. Weaver My Commission Expires: 5-1-2005
Notary Public # 01006609

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]