

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1978
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

15-147-00780-00-01

Operator's Full Name Petroleum Management, Inc.

Complete Address 400 North Woodlawn, Suite 201, Wichita, Kansas 67208

Lease Name Reece Well No. B-7 SWB

Location NE SE SW Sec. 5 Twp. 2 Rge. (E) (W) 18

County Phillips Total Depth 3469'

Abandoned Oil Well Gas Well Input Well X SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No. 731

Operation Completed: Hour 5:45 P Day 16 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 3469' ~~85578~~ csg set 181' cwc

5 1/2 csg set 3468' cw 150 sk cem.

5 1/2 csg top perf. (3373')

Filled 5 1/2 csg W/sd (3469'-3350') dumped 4 sk cem. W/dump bailer. (3350'-3320')

Cutoff & recovered 900' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water

W/100 lbs hulls -released cementing plug & pumped 120 sk cement & shutin.

300 lbs FSIP.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Massey
Well Plugging Supervisor

DATE 3-21-78

INV. NO. 6960-W