

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-147-00803-00-00

API Number 15- -

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name PHILLIPS PETROLEUM COMPANY

Complete Address BOX 287 GREAT BEND, KANSAS. 67530

Lease Name HUFFSTUTTER Well No. #4-2

Location SW-NE-NE Sec. 7 Twp. 2^s Rge. 18^w (East) (West)

County PHILLIPS Total Depth 3433 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor SUN OIL WELL CNT. + HELSO CASING PULLING

Address BOX 176 CHASE, KANS. License No. _____

Operation Completed: Hour: 12:25^{PM} Day: 26th Month: MARCH Year: 1981

The above well was plugged as follows:

8 7/8" 175^{lb} CUC -> 5 1/2" SET @ 3432^{FE}

PLUG. BACK. 3432^{FE} - PERK'S - 3309^{FE} TO 3381^{FE}

SHOT. PIPE 4 TIMES - RECOVERED 1195^{FE}

LOST TUBING AND RODS IN HOLE @ 2899^{FE}

AT. BOTTOM - SPOTTED - 15ST GEL. -> 35ST CNT. (COMMON) + 10ST GEL.

ORDERED 140ST 50% POZINIX 6% GEL. -> 27ST GEL. -> 5ST HULL'S + 8 7/8" PLUG.

PUMPED IN 8 7/8" WITH PUMP TRUCK.

PUT IN 5ST HULL'S -> 15ST GEL. -> 40ST CNT. -> 12ST GEL.

RELEASED PLUG. AND 40ST CNT. MAX PRESSURE 450^{PSI}

CEMENTED BY SUN CNT. 3-27-81

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 4-6-81

INV. NO. 5037-0