

DISTRICT CONSERVATION AGENT'S REPORT

B

15-147-00812-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 84-37

LOCATION E $\frac{1}{2}$ NW NW

SEC. 18 TWP. 2 RGE. 18

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4-A Lease Reece

Operator Bennett & Roberts Address Russell, Kans

Field _____ County Phillips

Total Depth 3415 Feet.

Plugging Contractor J & M Pipe Pulling

Plugging Contractor's License No. 11

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 170' circulated with cement - 5 1/2" at 3382' with 100

sax cement behind - Lane Wells plugs to ? - perforated at 3285'

Set plugs at 3270', sand and 4 sax cement with dump bailer,

pulled 1050' 5 1/2" - filled with mud to 170', set rock and 15 sax

cement - mud to 35', set rock and 10 sax cement to bottom cellar.

[Signature]
District Conservation Agent

Date 1-8-55

PLUGGING
FILE SEC 18 T 2 R 18W
BOOK PAGE 14 LINE 37

RECEIVED
STATE CORPORATION COMMISSION

1-14-55