

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-147-00811-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 84-38  
LOCATION NW SW NW  
SEC. 18 TWP. 2 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-5 Lease Reece

Operator Bennett & Roberts Address Russell, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3350 Feet.

Plugging Contractor J & M Pipe Pulling

Plugging Contractor's License No. 11

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3341' with 100 sax  
cement behind - Lane Wells plugs to 3332' - perforations at 3248'  
Filled with chat to 3240', set 4 sax cement with dump bailer -  
pulled 5 1/2" - filled with mud to 165', set rock and 15 sax cement -  
mud to 35', set rock and 10 sax cement to bottom cellar.

*[Signature]*  
District Conservation Agent

Date 12-28-54

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING

FILE SEC 18 TWP 2 RGE 18  
BOOK PAGE 84 LINE 38

CONSERVATION DIVISION  
1-3-55