

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-147-00810-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 84-39  
LOCATION SW NW NW  
SEC. 18 TWP. 2 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-2 Lease Reece

Operator Bennett & Roberts Address Russell, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3355 Feet.

Plugging Contractor J & M Pipe Pulling

Plugging Contractor's License No. 11

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 150' circulated with cement - 5 1/2" at 3348' with 75 sax  
cement behind - plugs to 3334' - perforated at 3310' -

Filled with chat to 3300', set 4 sax cement with dump bailer,

pulled 2500' 5 1/2" - heavy mud to 150', set 15 sax cement - heavy

mud to 35', set rock and 10 sax cement to bottom cellar.

*Edson Lee*

District Conservation Agent

Date 12-21-54

**PLUGGING**  
FILE SEC. 18 T. 2 R. 18W  
BOOK PAGE 84 LINE 39

12-23-54