

DISTRICT CONSERVATION AGENT'S REPORT

19-147-00809-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 84-40
LOCATION NW NW NW
SEC. 18 TWP. 2 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-1 Lease Reece

Operator Bennett & Roberts Address Russell, Kans

Field _____ County Phillips

Total Depth 3350 Feet.

Plugging Contractor J & M Pipe Pulling

Plugging Contractor's License No. 11

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 5 1/2" at 3345' with 65 sax
cement behind. Perforated at 3252',

Filled with chat to 3240', set 4 sax cement with dump bailer, pulled
1100' 5 1/2" - mud to 162' set rock and 15 sax cement - mud to 35', set
rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 1-2-55

PLUGGING
FILE SEC 18 T 2 R 18
BOOK PAGE 84 LINE 40

INDEXED
1-10-55
Conservation Division
Wichita, Kansas