

DISTRICT CONSERVATION AGENT'S REPORT

13-147-00805-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 101-19

LOCATION NE SW NE

SEC. 7 TWP. 2 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Reece

Operator Bennett & Roberts Oil Address Box 232 Russell, Kans

Field _____ County Phillips

Total Depth 3495 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3492' with
150 sax cement behind - cement to 3441' - perforations
~~3380'~~ 3391.

Filled with chat to 3380' - set 4 sax cement with dump bailer,
pulled approxo 1400' 5 1/2" - filled with mud to 180' - set
rock and 15 sax cement - mud to 35', set rock and 10 sax
ement to bottom cellar.

PLUGGING
FILE SEC 7 T 2 R 18 W
BOOK PAGE 101 OF 19

Eddard Latta
District Conservation Agent

Date 5-22-53

5-23-1953