

15-147-00779002-17

15th R

To: 6 010655 API NUMBER 15- Com 3-1951  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW NE SW, SEC. 5, T 2 S, R 18 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
5242  
1650 feet from S section line  
3630 feet from E section line

Operator License # \_\_\_\_\_ Lease Name Reece Well # B-6  
Operator: Petroleum Mgmt Inc. County Phillips 110.44  
Name & Address 700 S. Woodlawn Well Total Depth 3398 feet  
Wichita, Ks. Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 185

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor \_\_\_\_\_ Co. License Number 5242

Address \_\_\_\_\_ Same \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ AM Day: 17 Month: Feb Year: 19 89

Plugging proposal received from Don Keener

(company name) P.M.I. (phone) \_\_\_\_\_

were: Order 350 sks cement 65/35 Poz 10% Gel 2% Lite and 500# Hulls.

5 1/2" casing at 3398'. Holes in casing 950' to 1375' and 360' to 390'. Tubing parted at 2350'. Squeezed at 2300' w/250 sks cement.

Elev. 2151 = 1176'  
S.L.D. 1275'

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 17 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 2300' pumped down 130 sks cement w/100# Hulls. Circulated, pulled tubing to 1200' pumped down 15 sks cement w/25# Hulls circulated.

Pulled tubing. Squeezed casing w/100 sks cement and 275# Hulls 500# pressure circulated.

Pumped down 8 5/8" 20 sks cement w/50# Hulls. 700# pres.

RECEIVED STATE CORPORATION COMMISSION

MAR 07 1989 3-7-89

Remarks: Allied Cement Co. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 3-7-89

INV. NO. 24080

Feb. 9

Signed Dale F. Balthazor (TECHNICIAN)