

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21176-00-00
Spot: NENWNW Sec/Twnshp/Rge: 12-32S-42W
100 feet from N Section Line, 1180 feet from W Section Line
Lease Name: HARRISON Well #: 3-12
County: MORTON Total Vertical Depth: 5200 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4880 WITH 30 SX CMT
MSCC Size: feet: 3483
PROD Size: 7 feet: 5200 WITH 265 SX CMT
SURF Size: 9.625 feet: 1459 WITH 500 SX CMT

\$16900

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 05/14/2004 11:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SVCS Phone: (713) 627-6814

Proposed Plugging Method: SET CIBP ABOVE TOP PERFORATIONS WITH 10 SX CMT ON TOP. PUMP 50 SX CMT AT CASING SHOOTOFF POINT. PLUG AT 1500' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2004 7:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5157'. SET CIBP @ 4880'. SPOT 30 SX CMT ON CIBP THROUGH TUBING. LOAD CASING WITH MUD. SHOOT CASING AT 2250'. DID NOT COME LOOSE. SHOOT AT 1993'. CAME LOOSE. 1ST PLUG PULL OUT OF HOLE TO 1950'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 1500'. LOAD HOLE & PUMP 75 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 4TH PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5014	5040		
4964	4976		
4940	4958		

RECEIVED
JUN 08 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 1993' OF 7" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
PART II
(TECHNICIAN)

INVOICED

DATE 6-8-04
INV. NO. 2004061649

Form 2P-2/3