

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19001-00-~~00~~-01
Spot: SWNWSE Sec/Twnshp/Rge: 5-2S-18W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: IMM-C Well Number: 1
County: PHILLIPS Total Vertical Depth: 3485 feet

Operator License No.: 31569
Op Name: BACH OIL PRODUCTION
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 190 125 SX CMT
Production: Size 5.5 feet: 3484 150 SX CMT 113.26
Liner: Size feet:

Well Type: EOR UIC Docket No: E08461.10 Date/Time to Plug: 04/18/2001 9:00 AM

Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 543-5615

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel with 500# hulls.
Wireline measure 3475'. Top of fluid at 800'.
Casing squeeze at 2500' with 200 sxs.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/18/2001 10:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P.
Squeezed 40 sxs cement with 50# hulls mixed in cement.
Max. P.S.I. 200#. S.I.P. 100#.
Rigged up cementers to 5 1/2" casing.
Squeezed 225 sxs 60/40 pozmix - 10% gel plus 450# hulls down casing.
Max. P.S.I. 500#. S.I.P. 400#.

INVOICED

DATE 5-7-01

INV. NO. 2001061767

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 7 2001

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through:

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

B & R DRILLING, INC.

#1

1MM C

5-2-18W

6

SW NW SE

Contr.

PHILLIPS

Coun

E 2219

Comm.

Comp.

2-16-51

IP

105 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3340	-1121
LANS	3366	-1147
T.D.	3485	-1266

Casing

8" 180 CO 3485

5" 3485 PERF 3472-77


3462-67

1 1/2 BOPH/18 HRS

ACID 2000

7 BOPH/14 HRS

HUFFSTUTTER POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS