

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00777-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 5-2S-18W
330 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: REECE B Well Number: 4
County: PHILLIPS Total Vertical Depth: 3434 feet

Operator License No.: 31569
Op Name: BACH OIL PRODUCTION
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 182 w/125 sxs cmt. 8
Production: Size 5.5 feet: 3434 w/150 sxs cmt. 111.61
Liner: Size feet:

Well Type: EOR UIC Docket No: E08461.17 Date/Time to Plug: 04/18/2001 9:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION
Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 476-5254

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" liner at 3268' to surface - circulate with 200 sxs common cement.
Wireline measure to 3400'. Top of fluid at 800'+.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/18/2001 11:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P. Squeezed 40 sxs cement with 50# hulls mixed in cement.
Max. P.S.I. 200#. S.I.P. 150#.
Rigged up cementers to 5 1/2" x 4 1/2" casing.
Squeezed 160 sxs cement with 450# hulls mixed in cement.
Max. P.S.I. 1000#. S.I.P. 500#.

INVOICED
DATE 5-7-01
INV. NO. 2001061767

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 7 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through:

District: 04

Signed Dennis L. Hamel

(TECHNICIAN)

APR 30 2001

B & R DRILLING, INC.

#1 REECE B

5-2-1.8W
SW SW SW

6

Contr.

PHILLIPS

Coun

E. 2187

Comm.

Comp.

2-2-51

IP

100 BOPD

PHY POT

| Tops | Depth | Datum |
|------|-------|-------|
| | | |
| HEEB | 3284 | -1097 |
| | | |
| LANS | 3311 | -1124 |
| | | |
| T.D. | 3435 | -1248 |

Casing
 8" 182 CO 3412
 5" 3434 PERF 12 S, 3382-87
 ACID 2000
 SWB 8 BOPH

HUFFSTUTTER POOL

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

311