

6 010742

1-8 15-147-00778-00-06

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E 8461 Drilled 1951

NE SW SW SEC. 5, T 2 S, R 18 W/EX

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name Reece Well # B - 5

Operator: Petroleum Mgmt Inc.

County Phillips 115.21

Name & Address 400 N. Woodlawn

Well Total Depth 3545 feet

Wichita, Ks.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 179

Abandoned Oil Well Gas Well Input Well xx SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor P.M.I. License Number 5242

Address Same

Company to plug at: Hour: 2:00PM Day: 8 Month: Jan Year: 19 91

Plugging proposal received from Don Keener

(company name) Same (phone)

were: Order 50 sks common cement 350 sks 65/35 poz 8% gel 200 lbs. hulls.

Run wireline to t.d. 5 1/2 at 3414. Perf at 3318 - 3412. 4 1/2 liner at 3419 to

3545. Holes sq. from 1007 - 2780 w/1350 sks cement. Elev. 2177. top dakota 927.

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 6:00PM Day: 8 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Ran wireline to 3322. Pumped down casing 50 sks common cement and 250 sks 65/35 poz 8% gel and 100 lbs. hulls. 1500 lbs. working pressure.

Closed w/1000 lbs. Pumped down 8 5/8 100 sks cement 100 lbs. hulls. Working pressure 300 lbs. Closed w/100 lbs.

Remarks: allied Cement Co. (Sonny) (PMI Don Keener)

01-10-91
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE FEB 13 1991

INV. NO. 30721

File-S

Signed Dale F. Baltazor (TECHNICIAN) Dale F. Baltazor