

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20413-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 9-28S-35W
2991 feet from S Section Line, 2627 feet from E Section Line
Lease Name: ENGLISH H Well #: 2
County: GRANT Total Vertical Depth: 3130 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 2800 WITH 2 SX CMT
PROD Size: 4.5 feet: 3129 WITH 275 SX CMT
SURF Size: 8.625 feet: 762 WITH 375 SX CMT

8/01'73

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/17/2004 1:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PULL STRETCH. SHOOT OFF PIPE AT 800'. PULL TO 800' & PUMP 70 SX CMT. PULL TO 40' & PUMP 10 SX CMT TO SURFACE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2004 10:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3099'. 05/17/04: CIBP @ 2800' WITH 2 SX CMT. 1ST PLUG PULLED CASING TO 800'. CIRCULATED HOLE WITH MUD & PUMPED 70 SX CMT. 2ND PLUG PULLED UP TO 500'. SDON. 05/18/04: TAG TOC WITH WIRELINE AT 720'. PUMP 20 SX CMT AT 500'. 3RD PLUG PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
2976	2982		
2943	2963		
2922	2934		
2914	2918		

RECEIVED
JUN 08 2004
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 829' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY 25 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 6-8-04
VV. NO. 2004061651

Form *[Signature]*