

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-21278-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 23-28S-35W  
1250 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: MCCANDLESS A Well #: 4  
County: GRANT Total Vertical Depth: 3210 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

PROD Size: 5.5 feet: 3209 WITH 670 SX CMT  
SURF Size: 8.625 feet: 740 WITH 470 SX CMT

#104<sup>33</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2004 2:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. PLUG AT 1800' WITH 25 SX CMT. PLUG AT 760' WITH 85 SX CMT. FILL TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 05/14/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3144'. PUMP 400# HULLS WITH 25 SX CMT. 1ST PLUG PUMP MUD SPACER TO 1800' & PUMP 25 SX CMT. 2ND PLUG PUMP MUD SPACER TO 760'. PUMP 85 SX CMT FROM 760' TO SURFACE. CHECKED BACKSIDE, WAS CEMENTED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2935	2937		
2917	2921		
2892	2898		
2884	2886		

RECEIVED  
JUN 08 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PRT II  
(TECHNICIAN)

INVOICED  
DATE 6-8-04  
INV. NO. 200406161

Form CP 133