

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21120-00-00
Spot: SW Sec/Twnshp/Rge: 1-32S-42W
1368 feet from S Section Line, 1453 feet from W Section Line
Lease Name: RUSSELL Well #: 1-1X
County: MORTON Total Vertical Depth: 5250 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4900 WITH 30 SX CMT
MSCC Size: feet: 3307
PROD Size: 7 feet: 5242 WITH 84 SX CMT
SURF Size: 9.625 feet: 1478 WITH 397 SX CMT

#170⁶³

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 05/11/2004 9:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SVCS Phone: (713) 627-6814

Proposed Plugging Method: SET CIBP ABOVE PERFORATIONS WITH 10 SX CMT ON TOP. PUMP 50 SX CMT AT CASING SHOOTOFF POINT. PUMP 75 SX CMT AT 1500'. PUMP 50 SX CMT AT 600'. PUMP 15 SX CMT FROM 40' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2004 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5198'. PULL OUT OF HOLE WITH TUBING & PACKER. RUN IN HOLE WITH TUBING & SET CIBP @ 4900'. SPOT 30 SX CMT ON TOP OF CIBP. PULL OUT OF HOLE WITH TUBING. SHOOT CASING AT 3000' & 1500' DID NOT COME LOOSE. SHOOT CASING OFF AT 600'. CAME LOOSE. RUN IN HOLE WITH TUBING TO 3000'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 1500'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING. LOAD CASING WITH MUD & PUMP 50 SX CMT AT 600' THROUGH 7" CASING. GOOD CIRCULATION. PULL OUT OF HOLE WITH CASING TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5006	5022		
4930	4940		
4490	4491		

RECEIVED
JUN 08 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 600' OF 7".

Plugged through: TBG

District: 01

RECEIVED
MAY 24 2004
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED
DATE 8-8-04
WV. NO. 2004061649

Form CP 2/3