

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21177-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 12-32S-42W  
4080 feet from S Section Line, 2540 feet from E Section Line  
Lease Name: HARRISON Well #: 2-12  
County: MORTON Total Vertical Depth: 5200 feet

Operator License No.: 32782  
Op Name: DUKE ENERGY FIELD SERVICES, LP  
Address: 370 17TH ST., STE. 2500  
DENVER, CO 80202

CIBP Size: feet: 4888 WITH 30 SX CMT  
MSCC Size: feet: 3527 WITH 90 SX CMT  
PROD Size: 7 feet: 5191 WITH 57 SX CMT  
SURF Size: 9.25 feet: 1466 WITH 225 SX CMT

*\$169<sup>00</sup>*

Well Type: GWI UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2004 12:00 PM

Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE

Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGYFIEDL SVCS Phone: (713) 627-6814

Proposed Plugging Method: SET CIBP ABOVE TOP PERFS WITH 10 SX CMT. PUMP 50 SX CMT AT CASING SHOOTOFF POINT. PUMP 75 SX CMT AT 1500'. PUMP 50 SX CMT AT 600'. PUMP 15 SX CMT AT 40'.

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 05/18/2004 7:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5149'. SET CIBP @ 4888' WITH 30 SX CMT ON TOP THROUGH TUBING. LOAD HOLE WITH MUD. PULL OUT OF HOLE & LAY DOWN TUBING. PULL STRETCH. RUN IN HOLE & SHOOT PIPE AT 2820'. DID NOT COME LOOSE. SHOOT AT 2500', DID NOT COME LOOSE. SHOOT AT 2264', PULL 1 JOINT CIRCULATE HOLE WITH MUD. PUMP 50 SX CMT AT 2242'. GOOD CIRCULATION. PULL OUT OF HOLE WITH 7" TO 1500'. LOAD HOLE & PUMP 75 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 50 SX CMT. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5034	5060		
4980	4992		
4962	4976		
0	0		

RECEIVED  
JUN 08 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 2264' OF 7" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAY 24 2004  
KCC Dodge City

Signed Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 6-8-04  
QTY. NO. 2004061649

Form CP-2/3