

4-041573 4-26

15-147-30019-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 05-1965

C NE NW /4 SEC. 07, 02 S, 18 W
660 feet from N section line
1980 feet from W section line

Operator license# 5242

Lease Kanzelmeyer well # C-3

Operator: Petroleum Management, Inc.

County Phillips

Address: 1420 East Central
Wichita, Kansas 67230

Well total depth 3610 feet ^{117.32}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet
w/135 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 26 Month: April Year: 94

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone:

Were: 5 1/2" casing set @ 3610' w/230 sxs. cement. Perf. @ 3415' - 3473'. Anhy. @ 1720' - Dakota @ 1260'.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls and 7 sxs. gel.

RECEIVED
STATE CORPORATION COMMISSION
MAY 05 1994

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[], ⁵⁻⁵⁻⁹⁴

CONSERVATION DIVISION
Wichita, Kansas

Completed: Hour: 4:30P.M., Day: 26, Month: April, Year: 94

Actual plugging report: 4 1/2" casing - squeezed 25 sxs. cement with 200# hulls, followed with 7 sxs. gel, followed with 125 sxs. 60/40 pozmix - 10% gel with 200# hulls. Max. 500#. 8 5/8" S.P. - Squeezed 50 sxs. cement with 100# hulls. Max. 300# P.S.I.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did not observe the plugging.

Dennis L. Hamel

DATE MAY 09 1994

(agent)

INV. NO. 40401

Form CP-2/3

4-26