

6 041074

10-5 15-147-19065-00-01

API NUMBER 15- E-9,984

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

525E NW, SEC. 7, T 2 S, R 18 W/E

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT
3797

Operator License #

Lease Name Huffstutter Unit # 4 W 4

Operator: Larnite Inv. Ltd

County Phillips 112.22

Name & Address 701 W Georgia St.

Well Total Depth 3453 feet

S. 1500

Conductor Pipe: Size feet

Vancouver, British, Colombia
Canada Z7Y1A1

Surface Casing: Size 8 5/8 feet 164' w/125 s

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number

Address Oberlin, Ks.

Company to plug at: Hour: 9:00AM Day: 5 Month: Oct Year: 19 89

Plugging proposal received from Anthony Bach

(company name) I.T.I. (phone)

were: 5 1/2" casing set at 3453' w/150 sks cement: Perf 3336 - 3426:

Perf anhy at 1750' and base dakota 1250':

Ordered 400 sks 65/35 poz 8% gel w/1/4# f.c. plus 5 sks hulls.

OCT 30 1989
10-30-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30PM Day: 5 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1820'; spotted 280 sks cement w/

sks hulls to circ cement; pulled tubing sq add, 60 sks cement in casing.

Max 1000# psi S.I. 1000#. Hooked up to 8 5/8" S.P. pumped in 60 sks cement w/

sks hulls Max 300# S.I. 250# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

DATE 11-2-89

INV. NO. 26308

DEC 15 1989

FEB 09 1990

FORM CP-2/3
Rev. 01-84