

15-147-19064-0001 X 10-f
6 041076

Disc

API NUMBER 15-09-984

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW SW, SEC. 7, T 2 S, R 18 WEX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3797

Lease Name Huffstutter Unit Well # 3W01

Operator: Larnite Inv. Ltd
Name & Address 701 West Georgia St.
Suite 1500
Vancouver British Columbia
Canada Z7Y1A1

County Phillips 110.57
Well Total Depth 3402 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 143' w/125 sks

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Plainville, Ks. 67663

Company to plug at: Hour: _____ Day: 4 Month: Oct Year: 19 89

Plugging proposal received from Anthony Bach

(company name) L. I. L (phone) _____

were: 5 1/2" set at 3364' w/75 sks: Perf at 3316 - 3402

Perf at 1725' and at 1200'; Anhy and dakota.

Ordered 400 sks 65/35 poz 8% gel w/1/4# f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour 3:15PM Day: 4 Month Oct Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1700'; spot 275 sks cement w/4 sks hulls to circ.

Pulled tubing; sq add 50 sks cement in casing. Max 800# S.T. 500#. Hooked up 8 5/8" S.P.

Pumped 75 sks cement w/1 sk hulls. Max 400#. S.T. 200#.

OCT 30 1989
10-30-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I did / ~~did not~~ observe this plugging.

INVOICED

Signed Dennis J. Hamel
(TECHNICIAN)
Dennis Hamel

DATE 11-2-89

INV. NO. 26307

10-6 DEC 15 1989

FEB 09 1990

FORM CP-2/3
Rev. 01-84