

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20668-00-00  
Spot: SWNE Sec/Twnshp/Rge: 36-34S-35W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: KINNEY CHESTER SAND UNI Well #: 901  
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

COND Size: 20 feet: 20 WITH 2 YDS CMT  
PROD Size: 5.5 feet: 6745 WITH 175 SX CMT  
SURF Size: 8.625 feet: 1653 WITH 775 SX CMT

# 219<sup>38</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2004 2:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Revd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1680' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/20/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6688'. PUMP 300# HULLS WITH 25 SX CMT. PRESSURE TO 500# AND SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1680'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. SDON. 05/20/04: LOAD HOLE & PUMP 40 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6524	6536		

RECEIVED  
JUN 08 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2219' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAY 25 2004  
KCC Dodge City

Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 6-8-04  
INV. NO. 200406651

Form CP343