

6 010638

9-28

API NUMBER 15- 147-20,343-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis
Name & Address: 211 N. Broadway
Wichita, Ks.

_____ feet from S section line
_____ feet from E section line

Lease Name Imm Well # B-2

County Phillips 116.81

Well Total Depth 3594 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: 8:00 AM Day: 28 Month: Sept Year: 19 88

Plugging proposal received from Kelso

(company name) Kelso (phone) _____

were: 4 1/2" casing at 3593'. Perf 3340' - 3510'. Shot csg to 3290' and 4 sks cmt on

top. Order 200 sks cmt 60/40 Poz 8% Gel 500# Hulls 2 1/2 sks cement
Elev. 2174'

SLD 1350' Anhydrite 1600'

Top 824'

Base 1124' Plugging Proposal Received by _____ DFB
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 28 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Shot csg at 1623', ran rate, 5 bbls. mi. pumped down

csg 30 sks cement w/100# Hulls. Then, 2 1/2 sks. gel and wiper plug to 1300'. Shot csg
at 1233'. Pulled csg to 1100'. Pumped down csg 14 1/2" sks gel. Then, 100 sks cmt w/200#

Hulls, 300# max held 100# for 15 min. Pulled csg to 350'. Pumped down csg 50 sks cmt w/150#

Hulls. Circulated gel. Pulled csg. Capped w/10 sks cement and 50# Hulls.

Remarks: Allied Cement Co.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (could) observe this plugging.

DATE 10-25-88

INV. NO. 22686

Signed Dale F. Balthazor
(TECHNICIAN)
Dale F. Balthazor