


15-147-00811-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas



Locate well correctly on above Section Plat

Phillips County, Sec. 18 Twp. 2 Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner Bennett & Roberts Oil Operations
Lease Name Reese "A" Well No. 3
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10/24 19 48
Application for plugging filed 12/14 19 54
Application for plugging approved 12/15 19 54
Plugging commenced 12/21 19 54
Plugging completed 12/28 19 54
Reason for abandonment of well or producing formation Not profitable to operate

If a producing well is abandoned, date of last production Nov. 8 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Kansas City Depth to top _____ Bottom _____ Total Depth of Well 3350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	165'	None
				5 1/2"	3341'	2028'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with crushed rock to 3240', dumped 4 sax cement with dump bailer at 3240'. Top of cement 3220'. Filled hole with mud to 165', set rock bridge, dumped 15 sax cement. Top of cement 120'. Filled with mud to 35', set rock bridge, dumped 10 sax cement for cap.

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1955

CONSERVATION DIVISION
Wichita, Kansas

1-5-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J & M Casing Pulling Co.
Address Great Bend, Ks.


KANSAS
STATE OF ~~MISSOURI~~ KANSAS, COUNTY OF Russell, ss.
Harold Wurst

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 55

My commission expires 6/17/58 _____ Notary Public.



15-147-00811-00-00

B & R Drilling, Inc.
Reece #3

Sec. 18 Twp. 2 Rge. 18
County: Phillips, Kansas

Total Depth: 3350
Comm: 9/27/48 Comp: 10/7/48

Measurements from top
of rotary bushing:
Top Lansing K.C.-3248

Casing	cement
8 5/8 Set A @ 165'	125 sx - Circulated
5 1/2 Set @ 3341	100 sx

Formation:	Depth:
Surface Clay, post rock	30
Shale & post rock	60
Shale	165
Shale & Shells	940
Sand	963
Shale & Sand	1076
Sand	1101
Shale & Shells	1258
Sand	1320
Shale, Shells, & Sand	1380
Shale & Shells	1530
Shale & Sand, Red Bed	1560
Shales, Shells, Red Bed	1590
Shale & Shells	1670
Anhydrite	1715
Shale & Shells	2210
Shale & Lime	3260
Lime	3350

STATE OF KANSAS)
COUNTY OF RUSSELL) SS

I hereby certify that the above information is true and correct to
the best of my knowledge.

How Robert

Subscribed and sworn to before me this 13th day of October, 1948.

Clara L. Linn
Notary Public

My Commission Expires 6/17/50

PLUGGING
WELL SEC. 18 Twp. 2 Rge. 18
WELL PAGE 84 LINE 38

12-15-54