


15-147-00810-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Phillips County, Sec. 18 Twp. 2 Rge. 18W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner Bennett & Roberts Oil Operations  
Lease Name Reece A Well No. 2  
Office Address Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 6/30 1947  
Application for plugging filed Dec. 14 1954  
Application for plugging approved Dec. 15 1954  
Plugging commenced Dec. 15 1954  
Plugging completed Dec. 21 1954  
Reason for abandonment of well or producing formation Not ~~for~~ profitable to operate



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production Nov. 8 1954  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Depth to top Bottom Total Depth of Well 3352 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	156'	None
				5 1/2"	3348'	2489'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 3300',  
dumped 4 sacks cement with dump bailer, top  
of cement, 3280'. Filled hole with mud  
to 156', set 10' rock bridge, dumped 15  
sacks cement. Top of cement, 111'. Filled  
with mud to 30', set rock bridge, dumped  
10 sacks cement for cap.

JAN 3 - 1955  
CONSERVATION DIVISION  
Wichita, Kansas

1-3-55

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J & M Casing Pulling Co.  
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1954

Clawhammer  
Notary Public.

My commission expires 6/17/58

PLUGGING  
FILE SEC 18 T 2 R 18W  
BOOK PAGE 84 LINE 39

15-147-00810-00-00

Bennett & Roberts Oil Operations  
Reece #2

Sec. 18 Twp. 2 Rge. 18  
County: Phillips, Kansas

Total Depth: 3352  
Comm: 6/2/47 Comp: 6/14/47

Top Lansing K.C. 3253

Casing  
11 Jts. 8 5/8" Set at 156'  
108 Jts. 5 1/2" Set at 3348'

Cement  
100 sx  
75 Sx

Formation:	Depth:
Shale & Sand	40
Shale	70
Sand & Rock	95
Shale & Shells	685
Sandy Shale	900
Sand & Shale	960
Shale & Shells	1056
Sand, Shale & Shells of Pyt.	1410
Red Bed, Shale & Shells	1590
Sand	1640
Red Bed, Shale, & Shells	1675
Anhydrite	1697
Red Bed & Shells	1705
Red Bed, Shale & Shells	1850
Shale & Shells	2215
Lime	2290
Shale	2310
Lime	2325
Lime & Shale	2515
Lime	2570
Lime & Shale	2665
Lime	2685
Shale & Lime	2915
Shale & Shells	3030
Lime & Shale	3095
Lime	3140
Lime & Shale	3255
Lime	3352

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.


I hereby certify that the above information is correct to the best of my knowledge.

Sylvia Day

Subscribed and sworn to before me this 14th day of December, 1954.

Clare Hummel  
Notary Public

My Commission Expires 6/17/58



12-15-54