

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-00805-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Phillips County. Sec. 7 Twp. 2 Rge. 18 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW NE

Lease Owner Bennett & Roberts Oil Operations

Lease Name Reece "C" Well No. 5

Office Address Drawer 232, Russell, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2/20 19.51

Application for plugging filed 5/14 19.53

Application for plugging approved 5/15 19.53


Plugging commenced 5/16 19.53

Plugging completed 5/22 19.53

Reason for abandonment of well or producing formation Not enough oil to operate economically

If a producing well is abandoned, date of last production 5/1 19.53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Lansing Depth to top Bottom Total Depth of Well 3495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8" 5 1/2"	185' 3492'	None 1224'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock from 3495' to 3380'.
Dumped 4 sacks cement at 3380' with dump bailer. Top of cement 3350'. Filled hole with mud to 180', set rock bridge, dumped 15 sacks cement. Top of cement, 135'. Filled hole with mud to 35', set rock bridge, dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Box 711, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Donald L. Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Donald L. Roberts*
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of June 19.53

My commission expires 6/17/54

23-8390-s 6-51-20M

PLUGGING
FILE SEC 7 T 2 R 18W
BOOK PAGE 101 LINE 19

David L. ...
Notary Public.
JUN 1 1953
6-1-53
CONSERVATION DIVISION
Wichita, Kansas

B & R Drilling, Inc.
 Boone #5 # 5

25 04 35 Sec. 7-2-12
 Phillips County, Kansas

15-147-00805-00-00

Total Depth: 3495'
 Comm: 2-14-51
 Comp: 2-22-51

Casing

8 5/8" Set @ 125'
 5 1/2" Set @ 3492'

Content

125 feet of Ideal
 130 feet of other

Formation	Depth
Shale-Sand	125
Sand	125
Shale-Shells-Sand	125
Shale-Shells	125
Shale-Lime	125
Shale-Sand	125
Shale-Shells	125
Lime-Shells-Shale	125
Shale-Lime	125
Shale-Shells	125
Ft. Riley	125
Lime-Shale	125
Lime	125
Lime-Shale	125
Lime	125

STATE OF KANSAS }
 PHILLIPS COUNTY } ss

I hereby certify that the above information is true and correct to the best of my knowledge.

Jess Lake

Subscribed and sworn to before me this 20th day of February, 1951.

Mara Linnard
 Notary Public

VERIFIED

By commission expires 6-27-54
 5-15-53

PLUGGING
 FILE SEC 7-2-184
 UICF 101 UNIT 19