

15-183-00004-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Smith County. Sec. 34 Twp. 2 Rge. 11 (E) of SW 1/4
660' East, 330' South E 1/2

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner Charles A. Lasky
Lease Name Habiger
Office Address 809 Broadway Lubbock, Texas Well No. 1
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-16 19 54
Application for plugging filed 5-16 19 54
Application for plugging approved 5-16 19 54
Plugging commenced 5-16 19 54
Plugging completed 5-16 19 54
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner
Producing formation Depth to top Bottom Total Depth of Well 4250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215	8 5/8	5-2-54	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Set bottom plug at 210 feet, cemented with 15 sacks cement, circulated. Set top plug at 35 feet, cemented with 10 sacks bulk cement, circulated.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Clark Knight Drilling Co.
Address Great Bend, Kansas

STATE OF TEXAS, COUNTY OF LUBBOCK, ss.
Charles A. Lasky (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles A. Lasky
809 Bdwy, Lubbock, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 11 day of June, 19 54

My commission expires 6/1/55

Jeanelle Bagwell (Jeanelle Bagwell)
Notary Public.

PLUGGING
FILE SEC 34 T 2 R 11 W
BOOK PAGE 34 LINE 45

STATE CORPORATION COMMISSION
JUN 14 1954 6-14-54
CONSERVATION DIVISION
Wichita, Kansas

15-183-00004-00-00

WELL LOG

CHARLES A. LASKEY

LEASE - HABIGER
WELL #1

E 1/2 of SW 1/4
SECTION 34-2-11
SMITH COUNTY

TOTAL DEPTH: 4250' RB
COM: 4-30-54 COMP: 5-16-54
CONTRACTOR: CLARK KNIGHT DRILLING COMPANY
ROTARY: 0 - 4250'

ELEVATION: 1907 RB
PRODUCTION: D & A

CASING RECORD: 8 5/8" SET @ 215' CEMENTED W/100 SACKS
BULK CEMENT, CIRCULATED.

FIGURES INDICATE BOTTOM OF FORMATION

SURFACE SOIL	15'
SAND & SHALE	100'
SHALE & SHELLS	810'
LIME	820'
SAND	890'
SHALE & SHELLS	1075'
ANHYDRITE	1090'
SHALE & SAND	1120'
SAND	1165'
SHALE & SHELLS	1720'
LIME & SHALE	1960'
SAND	1985'
LIME & SHALE	2390'
SHALE & SHELLS	2670'
LIME	3305'
SHALE	3323'
SHALE & SAND	3430'
SHALE	3505'
SHALE & SAND	3705'
CHAT	3720'
SHALE & CHAT	3746'
CHERT & LIME	3827'
LIME	3959'
LIME & CHERT	4053'
LIME & SHALE	4203'
LIME	4250'

I HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL AS SHOWN ON THE DAILY DRILLING REPORT.

Charles A. Laskey

SUBSCRIBED AND SWORN TO BEFORE ME THIS 11 DAY OF ~~MAY~~ ^{June} 1954.

Jeanette Bagwell (Jeanette Bagwell)
NOTARY PUBLIC

MY COMMISSION EXPIRES:

6/1/55

PLUGGING
34-2-11W
34-2-45

6-14-54