

15-147-00771-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas. 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Center Huffstutter Unit

WELL NUMBER Jackson B #3

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 5 TWP. 2 RGE. 18 (EXTR) (W)

COUNTY Phillips

Date Well Completed 6/22/51

Plugging Commenced 7/30/86

Plugging Completed 7/30/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? Submitted with plugging application

Producing Formation Lansing/K.C. Depth to Top 3376' Bottom 3493' T.D. 3495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/K.C.	Oil & water	3426'	3493'	5 1/2"	3494'	-0-
				8 5/8"	167'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Pumped 175 sx cement, 5 sx hulls down casing @ 300 psi max. pres. S.I.P. 25 psi.

Pumped 75 sx cement down 8 5/8" casing @ 150 psi. S.I.P. 50 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 86

My Commission Expires:



AUG 8 1986

8-8-1986

Notary Public

15-147-00771-00-00

COMMENTS

B & R Drilling, Inc.  
Jackson "B" No. 3

L. B. STABLEFORD

NE SW NE Sec. 5-2-18W  
Phillips County, Kansas



Total depth: 3495'  
Comm: 5-29-51  
Comp: 6-8-51

Casing

8 5/8" Set @ 167'  
5 9/16" Set @ 3495'

Cement

125 sacks of Victor  
150 sacks of Victor

Formation	Depth
Shale-Shells-Sand	167
Shale	770
Shale-Shells-Sand	1340
Shale-Shells	1435
Sand-Shale	1530
Red bed-Shalls	1753
Anhydrite	1770
Shale-Lime, Shells	1795
Shale-Streaks of sand	2035
Lime-Shells-Shale	2160
Lime-Shale	3370
Lime	3411
Lime	3495

STATE OF KANSAS )  
                          )SS  
RUSSELL COUNTY )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

*Violet Zeller*  
-----

Subscribed and sworn to before me this 13th day of June, 1951.

*Clara Hummel*  
-----  
Notary Public

My commission expires: 6-17-54

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

JUL 24 1951