


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-00147-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 5 Twp. 2 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Nat'l Associated Pet. Company
Lease Name R. L. Morgan "A" Well No. 1
Office Address 502 Ritz Bldg., -Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 5, 1956 19
Application for plugging filed November 9, 1956 19
Application for plugging approved November 5, 1956 (verbal) 19
Plugging commenced 10:00AM November 5, 1956 19
Plugging completed 1:00PM November 5, 1956 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Topeka</u>		<u>3166'</u>	<u>3394'</u>			
<u>Lans-K.C.</u>		<u>3392'</u>	<u>3540'</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud 3560' to 198'
Cement from 198' to 180'
Heavy mud from 180' to 10'
Cement from 10' to surface.

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lewis Drilling Company
Address 607 Union National Bldg, Wichita, ~~Oklahoma~~ Kansas

11-10-56

STATE OF Kansas, COUNTY OF McPherson, ss.
Lawrence O. Tenk, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence O. Tenk, Jr.
Box 717, McPherson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 56

Donna Hunt

My commission expires May 6, 1957

Notary Public.

PLUGGING
FILE SEC 5 T 2 R 17W
BOOK PAGE 114 LINE 35

WELL LOG

15-147-00147-00-00

RECEIVED
11-13-56
NOV 13 1956

COMPANY National Associated Petroleum Co.

SEC. 5

NAT'L ASSOC. PET. CO.
T. 25
R. 17W

FARM Morgan "A"

NO. 1

LOC. NW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$

TOTAL DEPTH 3560'

COMM. 10-28-56


COMP. 11-5-56

COUNTY Phillips
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10
15	8 5/8" - 198'
12	6
13	5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 550	Surface soil & shale
550 - 590	Sand
590 - 975	Shale
975 - 1700	Sand & Shale
1700 - 2300	Shale & Shells
2300 - 3200	Lime & Shale
3200 - 3255	Cherty Lime & Shale
3255 - 3425	Lime & Shale
3425 - 3560	Lime
3560	T. D.

PLUGGING
FILE SEC. 5 T. 2 R. 17W
BOOK PAGE 114 LINE 35

State of KANSAS }
County of SEDGWICK } ss:

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Morgan "A" #1 well.

Subscribed and sworn to before me this 12th day of November 19 56

J. Fred Hambright
(J. Fred Hambright)

My Commission Expires: August 20, 1960

A. R. Derrington
NOTARY PUBLIC
(A. R. Derrington)

RECEIVED
NOV 13 1956
CONSERVATION DIVISION
White, Kansas