

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20413 0000

LEASE NAME English H

RECEIVED

JUN 08 2004

KCC WICHITA

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE# () OPERATORS LICENSE NO. _____

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-17-04 (date)
by Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Council Grove Depth to Top 2914 Bottom 2982 T.O. 3130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>762</u>	<u>8 5/8</u>	<u>762</u>	<u>0</u>
<u>Prod</u>			<u>3129</u>	<u>4 1/2</u>	<u>3129</u>	<u>829</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each:
Previously set CIBP + 2 sx 2800 to 2780 Shot + pulled 4 1/2 to 780
Attempt to circ hole w/mud. Mixed 70 sx plug from 780 to 580 (no circ)
woc tagged plug @ 720 Circ. hole w/mud, mixed 20 sx 500 to 435
10 sx 40 to 0 Cut off + capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 4th day of June, 2004



My Commission Expires: November 8, 2006

[Signature]
Notary Public