

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-21278-0060

LEASE NAME McCandless A

RECEIVED

JUN 08 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4

1250 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 23 TWP. 28 RGE. 35 (W)

COUNTY Grant

Date Well Completed 10-19-94

Plugging Commenced 5-14-04

Plugging Completed 5-14-04

KCC WICHITA

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, Ks. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-14-04 4-13-04 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? No

Producing Formation Council Grove Depth to Top 2884 Bottom 2937 T.D. 3210

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>				<u>8 5/8</u>	<u>740</u>	<u>-</u>
<u>Prod</u>				<u>5 1/2</u>	<u>3209</u>	<u>-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section.
Mixed 400 lb. hulls & 25 sx cmt to plug perfs from 2884 to 2684, pumped mud spacer to 1800, 25 sx plug 1800 to 1800, mud to 760, 85 sx cmt 760 to 0. Annulus was cmted to surface. Cut off & capped 5 1/2 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Sevier, ss.

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well, as filed, and that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 2528 Liberal, Ks. 67905



SUBSCRIBED AND SWORN TO before me this 4th day of June, 2004

[Signature]
Notary Public

My Commission Expires: November 8, 2006